
NOTES

- MANHOLES SHALL BE STANDARD REINFORCED CONCRETE SECTIONS 48" I.D. x 4'-0". IF MORE THAN ONE SECTION IS USED, INSTALL RAMNEK AT JOINTS.NO STEPS UNLESS THE DEPTH EXCEEDS 4' AND APPROVED BY THE CITY ENGINEER.
- INSTALL RAMNEK SEAL UNDER COVER FRAME ENTIRELY AROUND MANHOLE.
- SAMPLING PORT IS TO BE LOCATED IN A LOCATION WHERE IT CAN BE ACCESSED AT ANY TIME. LOCATION AS APPROVED BY CITY ENGINEER
- NO OTHER APPARATUS SHALL BE INSTALLED IN THE SAMPLING PORT MANHOLE.
- SAMPLING PORT MANHOLE LID SHALL NOT BE OF A 5. BOLT DOWN TYPE BUT SHALL BE CAST IRON ONLY AS APPROVED BY THE CITY ENGINEER.



PLAN VIEW 24" DIA. CAST IRON FRAME AND COVER PER WSDOT STANDARD PLAN B-30.70-03 4 4 4 4 4" SERVICE (TYP) DEPTH 48" DIA **PRECAST** STANDARD **SECTION** Z 4"X4"X4" TEE AREA UNDER DO NOT CAP ASSEMBLY SHALL BE CLEAR 24" PRECAST BASE MINIMUM **FLOW CAST IN PLACE** BASE CL 4000 CONCRETE SECTION A-A SECTION B-B

THE SERVICE.



City of Yakima - Standard Detail